

BRUHAT BANGALORE MAHANAGARA PALIKE


SCHEDULE - B

Name of work: Estimate for Improvements to Roads and Drains at Srinivasapura Murthy and Dasappa House Road in Ward No. 05 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates	
				KRIDL	
				In Figures	In Words
1	169.20	KSRRB 300 Excavation for road formation KSRRB 300-3. Earth work excavation and forming in embankment by manual means in ordinary soil with initial lead upto 15m, and lift of 1.5m, (when earth is taken from bank cutting of from borrow pits) including breaking of clods, spreading to required line and level, forming, and cost of all labour complete as per specifications. (excluding watering and compaction of earth) MORTH chapter 3. No. 141/ Item No. 19.3/ PWD SR 2015-16	cum	105.84	Rupees One Hundred Five and Eighty Four Paise Only
2	183.80	KSRRB 300-1. Earth work excavation by manual means in Hard Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 141/ Item No. 19.2/ PWD SR 2015-16	Cum	115.56	Rupees One Hundred Fifteen and Fifty Six Paise Only
3	463.65	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick Page No. 28/ Item No. 5.31.1/ PWD SR 2015-16	Sqm	663.12	Rupees Six Hundred Sixty Three and Twelve Paise Only
4	130.70	KSRRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16	Cum	5070.60	Rupees Five Thousand Seventy and Sixty Paise Only
5	7.02	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Page No. 23/ Item No. 5.6/ PWD SR 2015-16	cum	4135.32	Rupees Four Thousand One Hundred Thirty Five and Thirty Two Paise Only
6	5.85	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2015-16	Sqm	4905.36	Rupees Four Thousand Nine Hundred Five and Thirty Six Paise Only
7	15.30	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16/ Item No. 4.34/ PWD SR 2015-16	Sqm	270.00	Rupees Two Hundred Seventy Only

H.V. V. 
M. U. (M. U. 2) 25/11/16

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates	
				KRIDL	
				In Figures	In Words
8	2.08	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2015-16	cum	5491.80	Rupees Five Thousand Four Hundred Ninety One and Eighty Paise Only
9	13.00	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.1/ PWD SR 2015-16	Sqm	99.36	Rupees Ninety Nine and Thirty Six Paise Only
10	4.93	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastessisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2015-16	Cum	6198.12	Rupees Six Thousand One Hundred Ninety Eight and Twelve Paise Only
11	0.37	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2015-16	Qtl	64074.14	Rupees Sixty Four Thousand Seventy Four and Fourteen Paise Only
12	84.60	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Page No. 18/ Item No. 4.48/ PWD SR 2015-16	Cum	6332.04	Rupees Six Thousand Three Hundred Thirty Two and Four Paise Only
13	171.00	KSRRB M2600-3: (ii) Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification No. 2605, No. 233/ Item No. 31.3 PWD SR 2015-16	M	138.24	Rupees One Hundred Thirty Eight and Twenty Four Paise Only
14	846.00	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift No. 171/ Item No. 22.7/ PWD SR 2015-16	Sqm	97.20	Rupees Ninety Seven and Twenty Paise Only
15	211.20	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murum, watering charges & compaction by vibratory roller) MORTH Specification No. 305. (Page No. 144 & Item No. 19.60) PWD SR 2015--16	Cum	311.04	Rupees Three Hundred Eleven and Four Paise Only


 25/11/18

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates	
				KRIDL	
				In Figures	In Words
16	226.80	Precast slab 20mm and down size for slab (including steel reinforcement) including centring and shuttering machine mixed concrete laid in layers not exceeding 15cms thick well compacted cost of all materials labour HOM of machineries curing complete as per specifications c.c 1:1.5:3 Including all cost of Material (DATA RATE ENCLOSED) 10cm thick RCC pre cast slab	Sqm	1856.67	Rupees One Thousand Eight Hundred Fifty Six and Sixty Seven Paise Only
17	353.00	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	73.36	Rupees Seventy Three and Thirty Six Paise Only

EXECUTIVE ENGINEER-4
Signature of the Contractor
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

25/11/11